BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Name of the Work : Construction of compound to Division office building in ward no 08, kodigehalli

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	468.43	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications	cum	484.92	Rupees Four Hundred Eighty Four and Ninety Two Paise Only
2	22.05	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs using 40mm and down size graded granite metal, corse aggregates @ 0.85 cum and fine aggregtes @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	5510.16	Rupees Five Thousand Five Hundred Ten and Sixteen Paise Only
3	51.77	Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1: 6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. - Available stones	cum	4963.68	Rupees Four Thousand Nine Hundred Sixty Three and Sixty Eight Paise Only
4	15.52	Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1: 6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. - New stones	cum	5921.64	Rupees Five Thousand Nine Hundred Twenty One and Sixty Four Paise Only
5	69.03	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	sqm	153.36	Rupees One Hundred Fifty Three and Thirty Six Paise Only
6	6.69	Providing and laying in position plain cement concrete of mix 1:2:4 with cement at 240 kg, with 20mm and down size graded granite metal coarse aggregate at 0.69 cum and fine aggregates at 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted for coping including cost of all materials, labour, HOM of machinery, curing, complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	cum	6528.60	Rupees Six Thousand Five Hundred Twenty Eight and Sixty Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
7	169.81	Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/cum having a minimum average compressive strength of 4.00N/mm2 confirming to IS 2185(Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing , hire charges of machineries etc., complete as per specfications . KBS No.5.4 with solid concrete blocks of size 40x20x20cm	sqm	1038.96	Rupees One Thousand Thirty Eight and Ninety Six Paise Only
8	396.90	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications etc., complete with all leads and lifts as per the directions of the Enginee-in-charge of the work.	kg	102.60	Rupees One Hundred Two and Sixty Paise Only
9	313.85	Providing 12mm thick cement plaster in single coat with cement mortar 1:6 to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	Sqm	208.44	Rupees Two Hundred Eight and Forty Four Paise Only
10	313.85	Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work. with primer	sqm	110.16	Rupees One Hundred Ten and Sixteen Paise Only
11	148.00	Interlock tiles (PWDSR 2018-19, P.103, I. 14.7)	sqm	1198.80	Rupees One Thousand One Hundred Ninety Eight and Eighty Paise Only
12	353.40	Chainlink fencing	Rm	440.64	Rupees Four Hundred Forty and Sixty Four Paise Only
13	86.40	Rectangular poles fencing	Rm	927.72	Rupees Nine Hundred Twenty Seven and Seventy Two Paise Only
14	194.37	Chainlink fencing	Sqm	772.20	Rupees Seven Hundred Seventy Two and Twenty Paise Only
15	255.60	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications.	sqm	379.48	Rupees Three Hundred Seventy Nine and Forty Eight Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
16	28.75	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams.	cum	5770.64	Rupees Five Thousand Seven Hundred Seventy and Sixty Four Paise Only
17	1.404	Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications	Tonne	75255.760	Rupees Seventy Five Thousand Two Hundred Fifty Five and Seventy Six Paise Only
18	63.90	Providing and laying in position reinforced cement concrete M20 mix with stone aggregates 20mm and downsize for slab (including steel reinforcement) including centering and shuttering, maching mixed, concrete laid in layers not exceeding 15cm thick well compacted cost of all materials, labour, HOM of machineries, curing complete as per specifications.	Sqm	2100.00	Rupees Two Thousand One Hundred Only
19	398.17	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading with all leads and lifts as directed by the Engineer in charge of the work.	cum	87.56	Rupees Eighty Seven and Fifty Six Paise Only

25/07

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

25/07

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"NO CORRECTION NIL"
"OTS APPROVED"

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ.